

one cape
implementing solutions for clean water

Implementing Local Solutions: Projects Across the Cape

Moderator: Heather McElroy, Cape Cod Commission

Speakers: Sia Karplus, Consultant to Falmouth

Lindsey Counsell, Three Bays Preservation, Inc.

George Heufelder, Barnstable County Department of Health & Environment

Ray Cody, US Environmental Protection Agency



one cape
implementing solutions for clean water

Sia Karplus

DIRECTOR OF RESEARCH AT SCIENCEWARES, INC., CONSULTANT TO FALMOUTH

Panel | Implementing Local Solutions: Projects Across the Cape

Little Pond Oysters



00:01

HD

Shellfish and Water Quality Planning: A Team Effort

Falmouth Division of Marine and Environmental Services

**Falmouth Water Quality Management Committee
Department of Public Works/Wastewater Division
School for Marine Science and Technology (SMAST)**



**Presented to OneCape by:
Sia Karplus, Science Wares, Inc.
June 23, 2016**

Falmouth's Estuaries Restoration Plan

April 2011 Town Meeting unanimously passed Article 17, appropriating \$2.7 million to proceed with sewer design and alternative demonstration projects

Voters approved this measure on a town-wide ballot, supporting it by a 2:1 margin

January 10, 2014, Secretary of Office of Energy and Environmental Affairs issued a Certificate of Adequacy for Falmouth's Final Comprehensive Wastewater Management Plan (FCWMP). The Secretary's Certificate endorses sewerage Lower Little Pond watershed and gives the Town 5 years to evaluate alternatives elsewhere

Shellfish Cultivation

Permeable Reactive Barriers

Bournes Pond Inlet Widening

Denitrifying Septic Systems & Eco-toilets

Road Runoff Remediation

It all started with Little Pond:

Let's watch the video!

2 acres in Little Pond off Narragansett St.
Alternate area off Brockton St.



Little Pond Project Goals:

- Install a quantity of oysters that will yield a DETECTABLE change in water quality
- Monitor and measure water quality over the three year demonstration period
- Measure nitrogen uptake to establish TMDL-credit for oysters
- Monitoring and measure for Resource Protection goals of Conservation Commission
- Measure public acceptance
- Evaluate implementation logistics

2015 Project Implementation




- **June 2015: 2 million oyster seed installed in upweller**
- **July 2015: 2 million oyster seed planted in Little Pond**
- **August 29, 2015: Oysters moved to second growing location due to prolonged anoxic event**
- **November 2015: Division of Marine Fisheries (DMF)-approved Relay to West Falmouth Harbor, Green Pond**



2015 Green Pond Relay Location



2015 West Falmouth Relay Locations



Little Pond Monitoring Plan for MA DEP and Conservation Commission


- Water Quality “Grab-sampling” at 10 locations
- Turbidity
- In-situ sensors for data with high temporal resolution
- Flora and fauna
- Buffer to wetlands

2013 - 2015 Turbidity Data Analysis:

Oysters increase clarity of the water

- In 2013, 2014, light penetration increased at the site closest to the oyster rack, LP OYS2, and then increased at the site directly below LP OYS2
- Linear trend of decreasing light extinction coefficients from the head to the mouth of Little Pond when excluding the site closest to the oyster rack ($r^2=0.99$)
- Data more pronounced in 2013, associated with lower chlorophyll pigment concentration

**2015 showed marked
DECREASE in water
clarity – oysters removed
in August**



Conclusions:

- **Absolute TN levels in Little Pond did not change significantly from 2006 MEP findings**
- **Hypoxic conditions (low DO) in 2012 – 2015 consistent with conditions from 2006 MEP findings**
- **Deployment of oysters in Little Pond produced modest LOCALIZED water quality improvements**
 - *The primary mechanism of this water quality improvement appears to be the uptake of phytoplankton*
- **Several independent measurements support this conclusion:**
 - Turbidity, Pigments and TN increased when oysters were removed for September and October
 - In 2013, 2014, grab samples for chlorophyll α shows reduced phytoplankton at LP-1.3 on the ebbing tide
 - In 2013, 2014, grab samples for pheophytin a show an increase within the deployment area
 - In 2013, 2014, nutrient data show a decrease in total nitrogen (TN) at LP-1.3, within the Demo Site, compared to upgradient sites, on the ebbing tide
 - In 2013, 2014, nutrient data shows lower POC and PON at LP-1.3 than in stations above the Demo Site

Conclusions, ctd:

- Deployment of oysters in Little Pond did not have negative impacts to biota, water quality, buffer to resource areas
- Removal of oysters is correlated with decreased water clarity and increased pigments



Next Steps: Continue to evaluate shellfish potential in Falmouth's 13 other estuaries



Bournes Pond Shellfish Planning

- Bournes Pond is 153 acres
- 15 acres available for shellfish gear per Army Corps of Engineers rule
- Growing 500,000 oysters this summer
- Evaluating maximum numbers of oysters and quahogs



 = Approximately 2 acres

Other initiatives:

- Continued use of Little Pond as a nursery for growing oysters for one season
- Relay of oysters to other estuaries for harvest
- Budget neutral approach to municipal propagation:
 - Sale of larger (2") seed that would be too large for harvest at end of second growing season
- Oyster bed in West Falmouth Harbor
- Additional upweller (9 total)
- Quahog propagation




one cape
implementing solutions for clean water

Lindsey Counsell

EXECUTIVE DIRECTOR, THREE BAYS PRESERVATION, INC.

Panel | Implementing Local Solutions: Projects Across the Cape



Three Bays Restoration Implementation Project

Lindsey B. Counsell
Executive Director

Three Bays
Preservation, Inc.

www.3bays.org







Figure VI-4. Contour plot of average total nitrogen concentrations from results of the present conditions loading scenario, for the Three Bays system.



Massachusetts Estuaries Project's Threshold is the ideal level of nitrogen for a healthy water body



Three Bays - Pilot Areas

[Inquire Now](#)

[Quicklinks](#)

[Community Login](#)

[Give](#)



CAPE COD ACADEMY

[ABOUT](#)

[ADMISSIONS](#)

[SCHOOL LIFE](#)

[CALENDAR & NEWS](#)

[SUPPORT CCA](#)

[SUMMER PROGRAMS](#)



TAKE A
CLOSER
LOOK

OPEN HOUSE

Saturday, October 24th 12 PM to 2 PM

RSVP events@capecodacademy.org



- urine collection system
- fertigation application area



Quick disconnect to spray gun

Figure 3: Front View (Booms Down)

Extra hose in case you need to relocate selector valve










0-1 1-2 2-3 3-4 4-5 5-6

sDOT, & MassGIS




0-1 1-2 2-3 3-4 4-5 5-6 6-7 7-8 8-9 9-10

Sources: MassDEP, MassDOT, & MassGIS







NOTE: Utilities are approximate and NTS and
 loading may be needed to accommodate system



Note: all proposed pipe
 to be 12" Ductile Iron
 installed with a min.
 slope = 0.5%

Install (2) 4 ft Dia. catch basins
 w/ (2) 4" frames & grates
 Install (3) 200 gallon catch basins
 w/ 2" slope natural drain
 w/ (1) 4" frame & cover

- Install 12" x 24" manhole on back of building
- Install 12" x 24" manhole on back of building
- Install 12" x 24" manhole on back of building

**Drainage Improvement
 Oyster Place Road
 Cotuit, Mass.**

D.P.W. - Engineering Division



Prepared by: [Signature]
 Date: [Date]

















- Base Map
- Planning Scenarios
- Data Summary

Summarize by: Nitrogen Load

Existing
 Future
 Scenario



Results

Total Number of Properties Selected	281
Existing Sewered	0
Existing GWDP	1
Total Existing Nitrogen Load	2,108.10 kg/year


- Costs
- Cape Cod Commission
- Contact Us



Cape Cod Commission
3225 Main Street (Route 6A)
Barnstable, Massachusetts 02630
(508) 362-3828

Map Navigation

- Identify
- ✓ Draw a Polygon
- Add/Remove Selection



Questions





one cape
implementing solutions for clean water

George Heufelder

DIRECTOR, BARNSTABLE COUNTY DEPARTMENT OF HEALTH & ENVIRONMENT

Panel | Implementing Local Solutions: Projects Across the Cape



masstc

Massachusetts Alternative Septic System Test Center
A division of Barnstable County Department of Health
and Environment

Could sawdust play a role in saving our marine embayments?

*George Heufelder, Director
Barnstable County Department of Health and Environment
gheufelder@barnstablecounty.org*




THE BOTTOM LINE

Sawdust = Carbon

It appears that incorporating a source of carbon into the soil profile of a leachfield to support denitrification can significantly reduce the amount of nitrogen entering the groundwater from septic systems.


“unsaturated” design

Septic Tank effluent




Sample location


Layer Cake Total Nitrogen (TN) Data




“saturated” design




BLC Total Nitrogen



“silt” design



Silt and Influent TN



MASSSTC

The project is a collaborative effort that draws upon the combined expertise and ideas of many individuals including: Damann L. Anderson, P.E., a researcher of passive nitrogen removal systems for the State of Florida Onsite Sewage Nitrogen Reduction Study (FOSNRS); George Loomis, an onsite septic system specialist and published author from the University of Rhode Island; Dr. Will Robertson of the University of Waterloo; Jose Amador, a soil scientist at the University of Rhode Island; John Eliasson with the Wastewater Management Section of Washington State Department of Health's Division of Environmental Public Health; Dave Potts of Geomatrix LLC; and Rob Jamieson, Ph.D., P.Eng, Associated Professor and Canada Research Chair in Cold Regions Ecological Engineering with Dalhousie University's Environmental Engineering Program. More recently, Barnstable County Department of Health and Environment is collaborating with Suffolk County Health Department and New York and Stony Brook University, Center for Clean Water Technology.

This project was funded in part by a grant from the Massachusetts Department of Environmental Protection and the U.S. Environmental Protection Agency under the 319(b) Competitive Grant Program. Mention of any product or procedure does not constitute an endorsement and the opinions expressed herein do not necessarily reflect those of the supporting agencies. Partial funding was also supplied through MADEP as part of the Section 208 Project.



one cape
implementing solutions for clean water

Ray Cody

SENIOR STORMWATER POLICY ANALYST, US ENVIRONMENTAL PROTECTION AGENCY

Panel | Implementing Local Solutions: Projects Across the Cape

Green Infrastructure Implementation Case Study: Design and Construction of Stormwater Best Management Practice Retrofits for the Control of Nitrogen on Cape Cod


R. Cody
Surface Water Branch
U.S. EPA - Region 1



Site 1: Town of Barnstable

Hyannis Inner Harbor, Barnstable, MA


- parcel: 0.35 acres
- drainage area: 6.9 acres
- IC: 3.5 acres (~ 51% IC)
- MS4 trunk line runs through the site
- drains to Hyannis Inner Harbor
 - impaired for TN and fecal coliform
- Total attenuated watershed N load: 41.5%
- subwatershed N load reduction target (NRT): 19.6-52.8%
- percent NRT due to stormwater / IC: 21%



Site 2: Town of Chatham

Undeveloped Town parcel near Oyster Pond, Chatham, MA

- parcel: 3.19 acres
- drainage area: 16.9 acres
- IC: 5.7 acres (34% IC)
- MS4 trunk line runs by the site
- drains to Oyster Pond,
impaired for TN and fecal coliform
- watershed/subwatershed N load reduction target (NRT): 74-88.2%
- percent NRT due to stormwater: 15%



Site Constraints

Hyannis Inner Harbor, Barnstable, MA

- parcel: 0.35-ac, 0.19-ac available (54%)
- park site, high traffic area
- very shallow groundwater



Oyster Pond, Chatham, MA

- parcel: 3.19-ac, 0.33-ac available (10%)
- wetland complex
- shallow groundwater
- deep drain line



Barnstable N BMP Retrofit Construction



Barnstable N BMP Retrofit Construction



Barnstable N BMP Retrofit Construction

Site Access Logistics; GW



Bottom Liner Install

Barnstable N BMP Retrofit Construction



ISR Stone Delivery



Installing Top Liner and Biosoil over ISR

Barnstable Retrofit Completed; During Storm



Chatham N BMP Retrofit Construction



Existing Conditions



Site Clearing

Chatham N BMP Retrofit Construction



Site Clearing [cont.]



Rough Excavation

Chatham N BMP Retrofit Construction



Bottom Liner - ISR Stone



Diversion Structure

Chatham N BMP Retrofit Construction



Delivering ISR Stone



Biosoil Grading; Outlet Structure Array

Chatham N BMP Retrofit Construction



BMP Inlet and Structure Array



Access Road Gate

Chatham N BMP Retrofit



Completed BMP Retrofit

Performance Assessment

To Be Determined . . .

Approach: allow BMP anerobe populations to establish over ~1-year, then install monitoring equipment:

- sample inlet to BMP, outlet from BMP, existing drainage system bypass.
- sample each for **flow and nutrients** with auto-samplers and volunteers

Monitoring Plan and Quality Assurance Project Plan (QAPP) **currently under development**


Schedule:

- start fall 2016
- ~ 20 storm events per year
- 3+ years of performance monitoring

Complication: Barnstable – observed base flow; 17.5 gal/min; spring only?


Performance Assessment

Anticipated Performance:



Performance Assessment

Anticipated Performance:



Questions?



one cape

implementing solutions for clean water

June 23-24 | Resort and Conference Center at Hyannis